

Date of Issuance: 8/27/2026	Effective Date: 8/27/2026
Owner: Kingsbury County	Owner's Contract No.: 2023-006
Contractor: Asphalt Paving & Materials, Co.	Contractor's Project No.: NA
Engineer: Civil Design Inc	Engineer's Project No.: 2023-006
Project: Str. No. 39-070-126 Replacement & 425 th Ave reconstruction	Contract Name: Str. No. 39-070-126 – Kingsbury County

The Contract is modified as follows upon execution of this Change Order:

Description:

The Southeastern guardrail on the southern structure needs maintenance. The existing guardrail and wood posts will be removed. The new guardrail will be installed in kind with the existing guardrail.

An unknown existing concrete footing was discovered below the roadway within the proposed structure limits for Str. 39-070-126. Removal and disposal of the unforeseen footing was required which was beyond the current scope of work in order to facilitate the construction of the new box culvert. The soils around the new box culvert were not suitable for backfill. Additional borrow material was hauled in to backfill the structure. Contractor also placed owner provided topsoil material along the road. Additionally, this change order is to balance some of the final quantities.

Bid Item No.:

42	W Beam Guardrail with Wood Posts	+ 26 FT	\$107.00	+\$2,782.00
43	W Beam Guardrail Flared End Terminal	+ 1 Each	\$7,550.00	+\$7,550.00
44	Guardrail Removal	+ 1 LS	\$125.00	+\$125.00
49	Guardrail Delineators	+ 5 Each	\$36.00	+\$180.00
50	Footing Removal	+ 1 LS	\$10,204.10	+\$10,204.10
51	Temporary Fence	+ 410 LF	\$4.12	+\$1,689.20
52	Remove 18" CMP	+ 1 LS	\$2,357.15	+\$2,357.15
53	Install 24" CIPP Liner	+ 52 LF	\$295.00	+\$15,340.00
54	Install 18" Flared End	+ 2 EA	\$1,532.15	+\$3,064.30
55	Placing Topsoil (Midland Extra Work)	+ 1 LS	\$5,383.00	+\$5,383.00
6	Contractor Furnished Borrow Excavation	+ 1,988 CuYd	\$18.58	+\$36,937.04
9	Aggregate Base Course	+ 1,777.5 Ton	\$7.25	+\$12,886.88
10	Stabilization Type 1L Portland Limestone Cement	+ 18.15 Ton	\$244.0	+\$4,428.60
20	High Flow Silt Fence	- 206 LF	\$3.00	-\$618.00
25	Traffic Control Signs	- 96 SF	\$4.00	-\$384.0
27	Type 3 Barricade	+ 9 Each	\$100.00	+\$900.00
21	12" Erosion Control Wattle (14')	- 2 Each	\$32.00	-\$64.000
28	High Build Waterborne Pavement Marking Paint, White	- 6.5 Each	\$31.25	-\$203.13
29	High Build Waterborne Pavement Marking Paint, Yellow	+ 4.2 Each	\$31.25	+\$131.25
12	Asphalt Concrete Surfacing	+ 24.58 Ton	\$81.00	+\$1,990.98
40	Erosion Control Blanket	- 305 SY	\$1.50	-\$457.50
				<u>+\$104,222.87</u>

Attachments: RFP 2, 3, and 4: Footing Removal Quote and Culvert Lining Quote

CHANGE IN CONTRACT PRICE		CHANGE IN CONTRACT TIMES	
Original Contract Price:		Original Contract Times:	
\$ 3,287,773.31		Substantial Completion: <u>August 7, 2026</u>	
		Ready for Final Payment: <u>September 4, 2026</u>	
Change from previously approved Change Orders		No Change from previously approved Change Orders	
\$ 7,661.43		Substantial Completion: <u>August 7, 2026</u>	
		Ready for Final Payment: <u>September 4, 2026</u>	
Contract Price prior to this Change Order:		Contract Times prior to this Change Order:	
\$ 3,295,434.74		Substantial Completion: <u>August 7, 2026</u>	
		Ready for Final Payment: <u>September 4, 2026</u>	
Increase of this Change Order:		No Change of this Change Order:	
\$ 104,222.87		Substantial Completion: <u>August 7, 2026</u>	
		Ready for Final Payment: <u>September 4, 2026</u>	
Contract Price incorporating this Change Order:		Contract Times with all approved Change Orders:	
\$ 3,399,657.61		Substantial Completion: <u>August 7, 2026</u>	
		Ready for Final Payment: <u>September 4, 2026</u>	

RECOMMENDED:		ACCEPTED:		ACCEPTED:	
By: 	By: _____	By: _____	By: _____	By: _____	By: _____
Engineer (if required)	Owner (Authorized Signature)	Contractor (Authorized Signature)	Estimator & Project Admin.		
Title: <u>Vice President</u>	Title: _____	Title: _____	Title: _____		
Date: <u>8/27/2026</u>	Date: _____	Date: <u>8/27/2026</u>	Date: _____		
Approved by Funding Agency (if applicable)					
By: _____	Date: _____				
Title: _____					